

# Developing the first Nutrient Bank through stream restoration in Virginia

**Prepared For:  
EcoStream Conference  
August 14, 2018**

**Presented By:  
Kip Mumaw, PE**

**ECOSYSTEM  
SERVICES**





# Thanks

Reeves Family



# Claim

---

Stream restoration is now a nutrient and sediment credit generating practice in the Commonwealth of Virginia. The technical and regulatory requirements have many challenges and may shape the way restoration is conducted and where it occurs.

A photograph of a small stream flowing over a concrete structure, surrounded by green vegetation. The water is dark and rippling as it flows over the structure. The surrounding area is filled with various green plants and grasses.


# Talking points

- Regulatory Program
- Mossy Creek details
- The credit accounting process and attendant challenges

# Regulatory Highlights

---


- Deed of restrictions or conservation easement
- Financial assurances
- Long-term protection
- 6% of sales to water quality improvement fund (5% retirement of credits)
- Baseline practices
- Release schedule





# Qualifying Conditions


- > 100 linear feet
- Actively enlarging/degrading
- Not primarily undertaken for infrastructure protection
- Comprehensive approach/functional framework
- Must comply with State & Federal regulations
- 1<sup>st</sup> through 3<sup>rd</sup> order streams preferable



# Baseline

---

- Soil Conservation Plan
- Nutrient Management Plan
- Livestock exclusion
- Accounting for reductions from upstream BMPs
- Accounting for assumed 100% compliance with approved TMDL Action Plans
- 35' buffer on all perennial streams








# Regulatory Influences

- Preference for projects high in the watershed
- Preference for projects in watersheds with active development/markets
- Preference for projects in rural areas
- Preferences for wide floodplains
- Preference for highly eroded streams



# Nutrient Credit Market

Ches. Bay Sales History



# Mossy Creek Details

---

South Fork Shenandoah - Potomac Watershed

Watershed = 4.48 mi<sup>2</sup>

Impervious Cover = 0.55%

Spring-fed 3<sup>rd</sup> order stream

Restored length = 1,500 lf

Slope = 0.5%

Pre-restoration depth = +/- 4'

Pre-restoration width = 15'-20'

Average restored depth = 1'

Restored width = 9'

Sediment reduction = 13.75 tons

Total Phosphorus reduction = 70.17 lbs


Total Nitrogen reduction = 239.79 lbs





# Protocol 1: Sediment Prevented

- Erosion Estimate
  - BANCS: BEHI, NBS, Bankfull
  - **Bed pins (calibration), aerial imagery, BSTEM**
- Bulk Density
- Pollutant Concentrations
- Restoration Efficiency - 50%



# BANCS Results

Average Weighted Erosion Rate = 0.56  
ft/yr


Average height of bank = 3.60'

Annual estimated reduction:

Sediment = 18.96 tons

Phosphorus = 109.97 lbs

Nitrogen = 238.79 lbs







**EXISTING CONDITIONS**







**EXISTING CONDITIONS**








**EXISTING CONDITIONS**



# BEHI

## Best Practices


- Based on Bankfull discharge
  - Use multiple methods and look for converging evidence. At least 2!
- Confirmation bias & parameter assessment consistency
  - Field calibration
  - Assess parameters not banks (GPS Methodology)
  - Use survey data & processing techniques
  - Don't assess depositional areas





# NBS Best Practices

- What Level of investigation is appropriate?
  - All of them!
  - Look for converging evidence to support your decision. Beware of Bankfull observations in dynamic systems
  - Stream hydraulics is complicated...
  - Model it!



# Bulk Density Best Practices

- Measure bulk density in the field
  - Account for all soil types and stratification



Clay: 85 lb/ft<sup>3</sup>

Sand: 89 lb/ft<sup>3</sup>


Sandy Clay Loam: 94 lb/ft<sup>3</sup>

Silt: 86 lb/ft<sup>3</sup>

Silty Clay: 77 lb/ft<sup>3</sup>








Bulk density varied from 67.50 - 93.97 lbs/ft<sup>3</sup> over the site

# Protocol 2: Nutrient Processing during Base Flow

- Length of stream with Bank Height Ratio of one or less
- Determine median base flow depth
- Calculate hyporheic box(es)
- Calculate denitrification
- Check to make sure you're under the cap!



$$BF = a \ln(Q) + bQ + c$$

$$BF = a \ln(Q) + bQ + c$$

$Q$  = monthly average stream discharge

$BF$  = base flow fraction

$Q_s$  = monthly average surface runoff

$Q_g$  = monthly average groundwater discharge

$$Q = Q_g + Q_s$$

$$BF = \frac{Q_g}{Q_g + Q_s}$$


$$\frac{Q_g}{Q_g + Q_s} = a \ln(Q_g + Q_s) + b(Q_g + Q_s) + c$$

$$Q_s = \frac{1}{[a \ln(Q_g + Q_s) + b(Q_g + Q_s) + c]} Q_g - Q_g$$



# Protocol 2 Best Practices

- Median Base Flow Width
  - USGS regression
  - Monitoring data
  - Field measurements
  - Geomorphic observations w/ modeling
- Reduce hyporheic box if bedrock is encountered



$$BF = a \ln(Q) + bQ + c$$

$$BF = a \ln(Q) + bQ + c$$

$Q$  = monthly average stream discharge

$BF$  = base flow fraction

$Q_s$  = monthly average surface runoff

$Q_g$  = monthly average groundwater discharge

$$Q = Q_g + Q_s$$

$$BF = \frac{Q_g}{Q_g + Q_s}$$

$$\frac{Q_g}{Q_g + Q_s} = a \ln(Q_g + Q_s) + b(Q_g + Q_s) + c$$

$$Q_s = \frac{1}{[a \ln(Q_g + Q_s) + b(Q_g + Q_s) + c]} Q_g - Q_g$$

# Protocol 3: Floodplain Reconnection

- Develop hydrologic and hydraulic model to estimate volume of runoff & area of floodplain accessed
- Determine treatment efficiency
  - Ratio of watershed to floodplain
  - Ratio of total runoff volume to volume accessed by floodplain wetlands
  - Wetland removal efficiency
- Determine pollutant loading
  - Remove baselines and loading removed by upstream practices




Figure 5: Hydrograph comparing total outflow to treated overbank flow during the 10 yr



# Protocol 3 Best Practices

- Model calibration
- Determine what probability storm event has access to the floodplain
- Use hydraulic model to determine storm probability that equals 1' depth over floodplain wetlands





Figure 3: This pair of pictures was used to estimate the width of flow during a storm that occurred on July 7th, 2016































# Delivery Factors



# Delivery Factors



Total Nitrogen	Total Phosphorus	Sediment
0.357	0.493	0.664





**DURING CONSTRUCTION**







**DURING CONSTRUCTION**







**1 MONTH AFTER CONSTRUCTION**







**1 YEAR AFTER CONSTRUCTION**







**1.5 YEAR AFTER CONSTRUCTION**







**1.5 YEAR AFTER CONSTRUCTION**







# Developing the first Nutrient Bank through stream restoration in Virginia

Prepared For:  
EcoStream Conference  
August 14, 2018

**THANK YOU!**

**ECOSYSTEM  
SERVICES**